




**General Demolition Notes**

- Where floor transitions from new floor to existing floor, a floor transition strip is to be provided. A knock-down frame is to be provided in place of the existing frame where the opening is a part of corridor.
- Remove all existing flooring, ceiling tile, rubber base, etc. where shown to be replaced by new materials in the finish schedule. RE: Floors plans, RCP, and Finish Schedule
- Owner has right of refusal for all demo work. If not retained, GC to be responsible for disposal.
- Verify all existing conditions. Notify architect of any discrepancies between the existing conditions and these documents. The Contractor is to consider the additional work required by any discrepancies to be included in this Contract.
- Burying or Burning of materials will not be permitted on site.
- Repair any damage caused to building construction identified to remain.
- Refer to other discipline drawings for additional demolition information as noted
- Schedule with the Owner any demolition that involves exposing to the weather the interior portions of building to remain. This work is to be performed during good, dry weather or temporary waterproof barrier walls shall be constructed at all occurrences where the demolition exposes weather to the interior of portions of buildings to remain.
- Existing loose school property to be the responsibility of the school district, removal of property by owner to be coordinated between the contractor and school district.
- Where areas are removed or altered, patch, repair, & paint to match adjacent surface material and finish.
- Remove partitions and existing fixtures.

**Specific Notes**

- 02 41 19 006 Remove Ceiling Tile Only in the Room; repair grid as needed




**Ceiling Legend**

- Moisture Resistant Acoustical Lay In Ceiling
- Colored Acoustical Lay In Ceiling
- Vinyl Faced Acoustical Lay In Ceiling
- Gypsum Board Ceiling
- 2x2 Acoustical Lay In Ceiling
- Plaster/Stucco
- Concealed Fastener Painted Metal Soffit
- 2x2 Fluorescent Fixture
- Surface-Mounted Fluorescent Light Fixture
- Recessed Can Light Fixture
- HVAC Supply Grille
- HVAC Return Grille
- Exterior Wall Light
- Interior Wall Light
- Open to Structure (OTS)

**1 RCP - Demolition**  
3/32" = 1'-0"

**Not For  
Construction**



**Specific Notes**  
 22 47 13 001 Install double drinking fountain here; coordinate with mechanical & electrical drawings

**1** Ruleville Middle Main Building - New Construction  
 3/32" = 1'-0"

**Ruleville Middle School**  
 250 Oscar St, Ruleville, MS 38771

Schematic Design

Project No	005
Date	June 2021
Revisions	Rev Date

10/5/2021 11:24:18 AM  
 D:\my stuff\BUSINESS\SS\work\2019\dalePartners\21027- Sunflower County\modeis\21027 Ruleville Middle School.rvt



General RCP Notes


- All ceiling heights shall be same as existing or lower, unless noted otherwise.
- Contractor shall paint all surfaces above 12'-0" at wall, roof, and ceiling, as well as anything attached therein at all rooms labeled OTS, unless noted otherwise.
- Repair/replace any and all ceiling damaged due to construction activities.
- Bent ceiling grid damaged due to construction activities shall be replaced or bent to appear as new in shape.
- ACT in auditorium to be reveal edged

Specific Notes

- 09 51 23 001 Install new ceiling tile into existing grid here

Ceiling Legend

- Moisture Resistant Acoustical Lay In Ceiling
- Colored Acoustical Lay In Ceiling
- Vinyl Faced Acoustical Lay In Ceiling
- Gypsum Board Ceiling
- 2x2 Acoustical Lay In Ceiling
- Plaster/Stucco
- Concealed Fastener Painted Metal Soffit
- 2x2 Fluorescent Fixture
- Surface-Mounted Fluorescent Light Fixture
- Recessed Can Light Fixture
- HVAC Supply Grille
- HVAC Return Grille
- Exterior Wall Light
- Interior Wall Light
- Open to Structure (OTS)



1 RCP - New Construction  
3/32" = 1'-0"



Not For Construction

Ruleville Middle School  
250 Oscar St, Ruleville, MS 38771

Schematic Design

Project No 005  
Date June 2021  
Revisions Rev Date

A-401

Central Toilets

General Finish Plan Notes


1. All flooring transitions are to occur at center line of door panel.
2. New Fixture locations shall be coordinated with mechanical sheets.
3. Install new tile base at all walls in bathrooms
4. Install new grab bars at all ADA toilets
5. Install 1/2" drywall at upper wall (4'-0" AFF To 2" Above Ceiling) with adhesive and mechanical fasteners; finish and paint with epoxy
6. Install moisture resistant back board at all new tile.

Specific Notes

02 41 19 002	Dashed lines indicated extent of demoed work
02 41 19 003	Demo FRP & Base at walls; typical at all bathroom interiors unless otherwise noted
08 11 13 002	Install new 36" HM Door and Frame with new hardware
09 30 13 001	Install new floor tile; slope to floor drain is drain provided
10 21 13.19 001	Install new toilet partitions (typical)
10 28 13 001	Install wall hung mirror here; center over fixture unless noted otherwise
10 28 13 002	Install hand dryer here; coordinate with electrical & mechanical
22 42 00 001	Coordinate new fixture installations with mechanical, typical for new


General Demolition Notes

1. Where floor transitions from new floor to existing floor, a floor transition strip is to be provided. A knock-down frame is to be provided in place of the existing frame where the opening is a part of corridor.
2. Remove all existing flooring, ceiling tile, rubber base, etc., where shown to be replaced by new materials in the finish schedule. RE: Floors plans, RCP, and Finish Schedule
3. Owner has right of refusal for all demo work. If not retained, GC to be responsible for disposal.
4. Verify all existing conditions. Notify architect of any discrepancies between the existing conditions and these documents. The Contractor is to consider the additional work required by any discrepancies to be included in this Contract.
5. Burying or Burning of materials will not be permitted on site.
6. Repair any damage caused to building construction identified to remain.
7. Refer to other discipline drawings for additional demolition information as noted
8. Schedule with the Owner any demolition that involves exposing to the weather the interior portions of building to remain. This work is to be performed during good, dry weather or temporary waterproof barrier walls shall be constructed at all occurrences where the demolition exposes weather to the interior of portions of buildings to remain.
9. Existing loose school property to be the responsibility of the school district, removal of property by owner to be coordinated between the contractor and school district.
10. Where areas are removed or altered, patch, repair, & paint to match adjacent surface material and finish.
11. Remove partitions and existing fixtures.




1 Central Toilets - Existing

1/2" = 1'-0"



2 Central Toilets - New Construction

1/2" = 1'-0"



Wall Types

1/2" = 1'-0"

